

JR-Tech Pack & Handover

Delivery & installation plan, maintenance programme, investment summary, binder contents and day-0 automation — the execution half of the proposal.

PROJECT REF JRT-2026-AGL-01	PREPARED FOR Auntie Gaik Lean's Old School Eatery, Bishop Street, George Town
PREPARED BY JR-Tech Solution Sdn Bhd × TechNext	DATE 4 July 2026
REVISION R1	STATUS SAMPLE — illustrative figures

Contents

01 Delivery & installation plan — 5 phases, 7 weeks	Sheet 2
02 Maintenance programme — PM schedule, consumables, SLA	Sheet 3
03 Investment & quotation summary — RM185,000 + RM2,980/mo	Sheet 4
04 Proposal binder contents — all 20 documents, 4 packs	Sheet 5
05 Day-0 automation — signature to execution in Odoo	Sheet 6
06 Acceptance & signatures	Sheet 7

Basis of preparation. A 55 m² kitchen inside a category-II heritage shophouse on Bishop Street: no street-front crane access, a 1.1 m back-lane door, timber upper floor, and a 7-week window from signing to opening night. Every constraint below was surveyed in the first meeting and is reflected in the fabrication drawings of the Blueprint Pack. Figures are modelled for demonstration.

SECTION 1 Delivery & installation plan — 5 phases, 7 weeks

Fabrication runs in parallel at the JR-Tech workshop while the site is prepared, so the heritage building is only disrupted for the weeks that genuinely need it. The restaurant continues trading until the end of week 2.

PHASE	SCOPE	DURATION	CREW	OWNER DEPENDENCY
1 • M&E first fix	3-phase supply upgrade (38 kW connected load), sub-meter, new DB, water/drainage runs, hood ducting route agreed with heritage consultant	Wk 1-2	2 M&E + 1 electrician (licensed)	TNB application signed; landlord consent letter
2 • Delivery via back lane	All equipment through the 1.1 m back-lane door: oversized items (cold room panels, wok range chassis, dishwasher) split at the workshop into ≤1.0 m sections, moved on skates and stair-rollers, re-assembled in place; no façade or street closure needed	Wk 3 (2 nights, 22:00–06:00)	4 riggers + supervisor	Back-lane access notice to neighbours (JR-Tech drafts)
3 • Fabrication install	Custom stainless benching, wall cladding, shelving and	Wk 3-4	3 fabricators	Final finish choice (confirmed at signing)

	pass — pre-fabricated at JR-Tech workshop weeks 1-2, site-fitted and sealed			
4 • Connection & test	Gas (residual LPG line) and electrical termination, pressure and earth-leakage tests, hood balancing, dishwasher heat-recovery commissioning	Wk 5	2 technicians + certifying engineer	—
5 • Commissioning & training	Full-load cook tests on the actual menu (Curry Kapitan wok test, Perut Ikan simmer hold, Otak-otak steam batch), staff training, 2 rehearsal services, snag list closed, handover file issued	Wk 6-7	JR-Tech chef-trainer + PM	Kitchen team available for 3 training days

Programme — signing to opening night

ganttt title 7-week programme — Auntie Gaik Lean kitchen (JRT-2026-AGL-01) dateFormat YYYY-MM-DD axisFormat Wk %W section Workshop Custom fabrication build :fab, 2026-07-13, 14d Equipment split for lane access :split, 2026-07-20, 5d section Site M and E first fix, 3-phase upgrade :me, 2026-07-13, 12d Night delivery via back lane :del, 2026-07-27, 3d Fabrication install and cladding :inst, 2026-07-29, 10d Gas and electrical connection, tests :test, 2026-08-10, 5d section Handover Commissioning and cook tests :comm, 2026-08-17, 5d Staff training and

rehearsals :train, 2026-08-20, 5d Opening night :milestone, open, 2026-08-28, 0d

Why 7 weeks holds: the two slowest items — fabrication and the TNB 3-phase upgrade — start on day 1 in parallel. The night-delivery plan for the 1.1 m door was rehearsed on the workshop floor before quotation, so week 3 carries no discovery risk.

SECTION 2 Maintenance programme

Every visit below is a scheduled **Odoo Field Service work order** created automatically from the maintenance contract on day 0 — with the equipment register, checklist and sub-meter reading step attached. The programme is what the RM1,180/month maintenance line buys.

Preventive maintenance by equipment class

EQUIPMENT CLASS	DAILY (OPERATOR)	MONTHLY (JR-TECH VISIT)	QUARTERLY	ANNUAL
Induction wok line	Wipe-down, glass check	Coil fan filters, thermal scan	Board diagnostics, calibration	Full strip and service
Simmer / stockpot station	Surface clean	Element and probe check	Valve service	Pressure certification
Hood & demand-control fans	Baffle rinse	Belt/VSD check, grease cup	Duct inspection	Full duct degrease (fire cert)
Dishwasher (heat-recovery)	Strainer, wash arms	Descale check, dosing pump calibrate	Heat-exchanger service	Element and seal overhaul
Refrigeration & chiller	Door seals, temps log	Condenser clean, gas pressure	Compressor health check	Refrigerant certification
Steamer / grill	Drain and wipe	Gasket and burner check	Descale	Overhaul

Consumables & spares held for this kitchen

ITEM	WHERE HELD
------	------------

Dishwasher dosing tubes, wash arms, curtains	On-site spares box
Hood grease filters (spare set)	On-site spares box
Induction wok control board + glass	JR-Tech Penang store (4h)
Fridge door gaskets, thermostat probes	JR-Tech Penang store (4h)
Detergent / rinse / sanitiser stock	Auto-resupply, min-level trigger

Chemical auto-resupply: the RM1,800/mo JR-Chemical subscription ships on consumption, not on a fixed calendar — dosing-pump counters are read at each monthly visit and Odoo raises the resupply delivery automatically.

Response SLA

TIER	COVERS	RESPONSE
P1	Wok line or dishwasher down	4 hours, same-day fix target
P2	Any other equipment fault	Next working day
P3	Cosmetic / non-blocking	Scheduled with next PM visit

P1 is defined by the Financial Pack: the wok line is the constraint station and the dishwasher is the only single point of failure — one lost service is $\approx$ RM5,000–7,300 of revenue. Every callout, response time and part used is logged on the Odoo work order, so SLA performance is a report, not a promise.

SECTION 3 Investment & quotation summary

One number, fully itemised in the referenced schedules — no provisional sums, no "subject to site" lines. The equipment schedule referenced below is the priced blueprint schedule in the Blueprint Pack (doc 04).

One-time investment

LINE	REFERENCE	RM
Equipment — cooking, wash, refrigeration (brand items)	Blueprint schedule §E1-E14	102,400
Custom stainless fabrication — benching, cladding, pass, shelving	Fabrication drawings F1-F6	46,200
Installation, M&E & 3-phase upgrade, delivery & rigging (back-lane plan)	Section 1 of this pack	28,400
Commissioning, cook tests & staff training	Phase 5	8,000
Total investment	—	185,000

Payment milestones — 40 / 30 / 20 / 10		
MILESTONE	%	RM
On signing (fabrication + brand POs released)	40%	74,000

On delivery to site (end week 3)	30%	55,500
On connection & test complete (week 5)	20%	37,000
On handover acceptance (opening week)	10%	18,500

Each milestone is an Odoo invoice raised automatically when the project stage closes — the owner never chases paperwork, and neither do we.

Recurring services — RM 2,980 / month

SERVICE	WHAT IT INCLUDES	RM / MONTH
JR-Tech maintenance contract	Monthly PM visit, quarterly & annual programme (Section 2), P1 4-hour SLA, sub-meter reading & report	1,180
JR-Chemical subscription	Dishwasher detergent & rinse, degreaser, sanitiser — auto-resupply on consumption	1,800
Total recurring	Single monthly Odoo subscription invoice	2,980

SECTION 4 Proposal binder contents

Everything the owner holds before signing — 20 documents across the four packs. Ticked items are rendered in this sample dossier; the remainder are produced in full on a live engagement.

#	PACK	DOCUMENT	FORMAT	IN THIS SAMPLE
01	Blueprint	Kitchen layout plan — 55 m ² , zones & flows	PDF / DWG	✓
02		M&E drawing — power, water, drainage, hood ducting	DWG	—
03		3D walkthrough renders	PDF	✓
04		Priced equipment schedule (brand + fabrication)	PDF / Odoo	✓
05		Heritage compliance notes (MBPP / George Town WHS)	PDF	—
06	Operations	Station map & staff positioning	PDF	✓
07		Prep & service workflow (menu-anchored)	PDF	✓
08		Roster model — 7 kitchen heads, 2 services	PDF / Odoo	✓
09		Food-safety & cleaning schedules	PDF	—
10		Opening / closing checklists	PDF / Odoo	—
11	Financial	Normal-day output model — 130 covers, RM12,350	PDF / Odoo	✓
12		Monthly P&L projection, ramp & break-even	PDF / Odoo	✓
13		Savings case vs typical kitchen	PDF	✓

14		Sensitivity & assumptions register	PDF	✓
15	JR-Tech & Handover	Delivery & installation plan (7-week gantt)	PDF / Odoo	✓
16		Maintenance programme & SLA	PDF / Odoo	✓
17		Quotation — RM185,000 + RM2,980/mo, milestone terms	PDF / Odoo	✓
18		Draft maintenance & chemical subscription agreements	PDF	—
19		Warranty register (per-equipment terms)	Odoo	—
20		Handover file — test certs, as-builts, training records (issued at week 7)	PDF / Odoo	—

SECTION 5 Day-0 automation — signature to execution

Because the four packs were modelled in Odoo before signing, the signature is not the start of planning — it is the start of execution. The moment Auntie Gaik Lean's agreement completes in Odoo Sign, the following chain fires without anyone re-keying a number.

flowchart TD
A["Agreement signed in Odoo Sign"] --> B["Sales order JRT-2026-AGL-01 confirmed"]
B --> C["Project created with 7-week plan and 5 phases"]
B --> D["Fabrication manufacturing orders released to workshop"]
B --> E["Purchase orders issued to brand suppliers"]
C --> F["Delivery schedule booked - night back-lane slots, week 3"]
B --> G["Maintenance contract activated - RM1,180/mo"]
B --> H["Chemical subscription activated - RM1,800/mo"]
G --> I["12 months of Field Service PM work orders generated"]
B --> J["Milestone invoice 1 issued - 40 percent, RM74,000"]
C --> K["P and L budget lines loaded to Accounting for variance tracking"]

The punchline of the method: planning is done *before* signing, so execution starts the *same day*. On the afternoon of signature the workshop is cutting stainless, the brand POs are out, the week-3 delivery nights are booked, and the first milestone invoice is in the owner's inbox — with the 7-week clock already running.

SECTION 6 Acceptance & signatures

Acceptance of this pack confirms the delivery plan (Section 1), maintenance programme and SLA (Section 2), investment and payment terms (Section 3), and authorises the day-0 automation chain (Section 5) upon execution of the main agreement.

For the Owner

Auntie Gaik Lean's Old School Eatery
Name · NRIC · Date

For JR-Tech Solution Sdn Bhd

Name · Designation · Date

Witness

Name · NRIC · Date

Date of execution

DD / MM / YYYY · George Town, Penang

Next steps

- 1 Sign via Odoo Sign** — the link in the covering email opens this binder for e-signature; day-0 automation fires on completion.
- 2 Confirm landlord consent & TNB application** — the only two owner dependencies on the critical path (week 1).
- 3 Nominate the kitchen team** for the three training days in weeks 6–7.
- 4 Week-3 access notice** — JR-Tech drafts the back-lane notice to neighbouring lots; owner countersigns.
- 5 Opening night, end of week 7** — with the Odoo dashboard live against the Financial Pack baseline from day one.

